Key Guidance This section provides a quick overview of some of the key concepts in Army risk assessment. Refer to Notes Likelihood (L) Impact (I) **Risk Score Calculation** section for further information. The first line of the risk assessment table, below, shows an illustrative example. 1 - Remote / Rare 1 – Minor Hazard is anything that may cause harm, e.g. working at height on a ladder. 5 10 15 20 25 2 - Unlikely 2 - Moderate Risk is the chance that someone or something could be harmed by the hazard, measured by combining (multiplying) the likelihood of it happening with its impact (severity). For example, there may be a 'possible' likelihood that someone that is not 3 – Possible 3 – Major 4 8 12 16 20 competent could fall from a ladder (3 rating - see right) combined with a 'moderate' impact of multiple injuries (2 rating), which 4 - Probable 4 - Severe creates a score of 6 (low risk). However, the risk should be reduced to as low as reasonably practicable (ALARP) through the 3 3 9 12 15 Multiplied implementation of control measures, such as ensuring that only trained people climb the ladder. 5 - Critical 5 – Highly Probable **IMPACT** Dynamic Risk Assessment compliments generic and specific risk assessment. Regardless of completing this AF 5010, it is (Almost Certain) 2 8 10 beholden on the person creating the risk to continue to monitor the activity and the control measures. Any changes to the Note: impact number activity (including the environmental conditions) or the control measures, must be addressed via the mechanism of a dynamic is unlikely to change 5 risk assessment such that risks remain ALARP. with control Note however that persons undergoing training cannot be deemed competent until their capability is properly assessed 2 3 measures 4 5 **LIKELIHOOD 5 Step Process** Step 1 – Identify the Step 2 – Decide who might be Step 3 – Evaluate the risks and decide Step 4 – Record your significant findings and include in Ex / Coord instructions as Step 5 – Review your risk assessment and hazards harmed and how on precautions (control measures) necessary. Implement control measures update as necessary

Dept / Sub-Unit / Unit / Formation:	203 Multi Role Medical Regiment	Assessor (No, Rank, Name):	24801730 Maj McGuffie
Activity (SSW) / Exercise (SST):	Site Risk Assessment	Assessor's signature:	
Generic or Specific Risk Assessment:	Generic	Assessment Date:	04 July 24
Relevant Publications / Pamphlets / Procedures:	 A. ACSO 1200 B. JSP 375 Part 2 Vol 1 (Chaps) and Vol 3 (High Risk) C. JSP 317 Storage and Handling of Fuels, Lubricants and Associated Products. D. JSP 319 Safe Storage and Handling of Gases E. JSP 418 Management of Environmental Protection in Defence F. DSA 03. OME Part 2 Chap 12 Para 5.30: Amnesty Boxes for Ammunition & Explosives 	· · ·	04 July 25

(a)	(b)	(c)	(d)	(e)	(f)	(g)	(h)	(i)	(j)	(k)	(I)	(m)	(n)
Ref	Activity / element (Step 1a)	Hazards identified (Step 1b)	Who or what might be harmed and how, e.g.	Existing control measures (Step 3a)		ssessmen kisting co		Is residual risk acceptable in the context of risk	Reasonable additional controls		ment with a trol measur		List required action(s) to instigate controls
			Military personnel - fatality Civ staff / contractors - injury General public - injury Environment - spill (Step 2)		L (1 to 5) (Step 3b)	I (1 to 5) (Step 3c)	Score (L x I) (Step 3d)	appetite for the activity? (Yes / No) – Refer to Risk Score Calculation above If Yes, move to column (n). If No, identify additional controls (Step 3e)	that can be implemented to reduce risk to ALARP (Step 3f)	L (1 to 5) (Step 3g)	I (1 to 5) (Step 3h)	Score (L x I) (Step 3i)	(Step 3j)
1		Trespassers Theft, vandalism, destruction of property, building damage or sabotage and/ or direct violence.	Site personnel (mil and civil servants), visitors or site contractors or tresspassers: Becoming trapped Falling from height Being hit by falling objects Exposure to harmful or hazardous substances, being hit by moving vehicles Physical violence	Site is fenced with warning signs displayed in areas where razor wire adorns the top at or below eye level and borders public access ways. Security gates at front and side with controlled access through keypad code. Known hazards on site secured and/ or sign posted. Site employees remain vigilant, with a staff presence in and around the site. Security cameras and alarms installed and used to visually screen visitors.	1	3	3	Yes					QM/RQMS To ensure compliance with site security procedures for access and egress from the site. (Part One Order repeats) Signs required for fence lines where razor wire adorns the top at or below eye level.

(a)	(b)	(c)	(d)	(e)	(f)	(g)	(h)	(i)	(j)	(k)	(I)	(m)	(n)
Ref	Activity / element (Step 1a)	Hazards identified (Step 1b)	Who or what might be harmed and how, e.g.	Existing control measures (Step 3a)		ssessmen disting cor		Is residual risk acceptable in the context of risk	Reasonable additional controls		ment with a		List required action(s) to instigate controls
			Military personnel - fatality Civ staff / contractors - injury General public - injury Environment - spill (Step 2)		L (1 to 5) (Step 3b)	(1 to 5) (Step 3c)	Score (L x I) (Step 3d)	appetite for the activity? (Yes / No) – Refer to Risk Score Calculation above If Yes, move to column (n). If No, identify additional controls (Step 3e)	that can be implemented to reduce risk to ALARP (Step 3f)	L (1 to 5) (Step 3g)	I (1 to 5) (Step 3h)	Score (L x I) (Step 3i)	(Štep 3j)
				Young persons (Cadets) supervised from point of entry to departure after their training events by adult instructors.									
				Adult instructors facilitate the access and egress of all cadets using the pedestrian gates only.									
				Cadets are not to operate the vehicle gates under any circumstances.									
				No vehicular access for parents dropping or collecting children from inside the site.									
				Information communicated to the Cadet CoC and included in the MOA. Signed by lodgers occupying the site.									
2		Gas leak Loss of Services Suspect package Fuel Spill Major Occurrence	Site personnel (mil and civil servants), visitors or site contractors or tresspassers: Cuts abrasions, crush injuries thermal or chemical burns, being overcome by smoke suffocation, carbon monoxide poisoning, sprains, impact injuries, puncture wounds, fractures, becoming unconscious, property damage, building collapse. Or Environmental pollution incident.	Emergency procedures established and tested periodically, with evidence documented. Emergency "Actions on" displayed on the main SHEF noticeboard with recognised muster points. Signs posted at every fire point identifying general assembly points. Emergency exits identified, emergency lighting operable and mainatined. Qualified FAW/ EFAW or appointed persons to support Sqn work patterns. Emergency contact details displayed (SHEF noticeboard) with emergency shut shown procedures, including locations and key holders.		3	3	Yes					QM/RQMS Ensure All personnel. are briefed and practised on the reaction to an emergency situation on an annual basis, with records kept.

(a)	(b)	(c)	(d)	(e)	(f)	(g)	(h)	(i)	(j)	(k)	(I)	(m)	(n)
Ref	Activity / element (Step 1a)	Hazards identified (Step 1b)	Who or what might be harmed and how, e.g.	Existing control measures (Step 3a)		ssessmen cisting co		Is residual risk acceptable in the context of risk	Reasonable additional controls		ment with a trol measur		List required action(s) to instigate controls
			Military personnel - fatality Civ staff / contractors - injury General public - injury Environment - spill (Step 2)		L (1 to 5) (Step 3b)	I (1 to 5) (Step 3c)	Score (L x I) (Step 3d)	appetite for the activity? (Yes / No) – Refer to Risk Score Calculation above If Yes, move to column (n). If No, identify additional controls (Step 3e)	that can be implemented to reduce risk to ALARP (Step 3f)	L (1 to 5) (Step 3g)	I (1 to 5) (Step 3h)	Score (L x I) (Step 3i)	(Step 3j)
3		Inappropriate or negligent storage of	Site personnel (mil and civil servants), visitors or site	Fire Safety is managed by the appointed UFSM in	1	3	3	Yes					UFSM/QM
		products or Substances/	contractors or tresspassers	liaison with the local DFRMO rep and RFCA. Fire training carried out annually under the direction of the UFSM (RSM), to									Monitor and maintain compliance with site fire safety standards and maintenance of Fire trained personnel.
				include evacuation drills. (Documented in fire diary).									UFSM – is to ensure Regular Fire meetings are carried out and any
				Liaison with local brigade established - contact telephone numbers available in Duty/ SHEF Folder									risks identified within the units Fire Plan are raised to the HoE and QM (USA).
				Alarms, appliances, emergency lighting checked and tested. (Documented in fire diary). Storage of flammable									UFSM is to ensure adequately trained persons are appointed.
				liquids, gases, substances, and materials in compliance with MOD standards. Ref C&D.									Line Managers are to ensure all their staff receive Fire awareness training annually and this is recorded.
				Site housekeeping maintained to minimise potential fire loading.									
				Documented workplace inspections and safety tours carried out periodically.									
				Flammable/combustible materials kept to a working minimum, no accumulation and stored appropriately.									
				Relevant signs & notices posted around the site.									

(a)	(b)	(c)	(d)	(e)	(f)	(g)	(h)	(i)	(j)	(k)	(I)	(m)	(n)
Ref	Activity / element (Step 1a)	Hazards identified (Step 1b)	Who or what might be harmed and how, e.g.	Existing control measures (Step 3a)		ssessmen cisting co		Is residual risk acceptable in the context of risk	Reasonable additional controls		ment with a		List required action(s) to instigate controls
			Military personnel - fatality Civ staff / contractors - injury General public - injury Environment - spill (Step 2)		L (1 to 5) (Step 3b)	I (1 to 5)	Score (L x I) (Step 3d)	appetite for the activity? (Yes / No) – Refer to Risk Score Calculation above If Yes, move to column (n). If No, identify additional controls (Step 3e)	that can be implemented to reduce risk to ALARP (Step 3f)	L (1 to 5) (Step 3g)	I (1 to 5) (Step 3h)	Score (L x I) (Step 3i)	(Step 3j)
4	Explosives	Incorrect/ negligent storage or disposal of Ordnance, Munitions or	Site personnel (mil and civil servants), visitors or site contractors or tresspassers	The site is licensed for the natures it is authorised to hold with relevant signs &	1	3	3	Yes					QM/RQMS (T) Ensure Site orders and
		Explosives (OME) Introduction of contraband	Creation of an explosive atmosphere and/ or propagation of fire, blast type injuries and/ or property damage. Possible enforcement action and reputational damage.	notices displayed. Policies and procedures for disposal and removal of OME established and effectively communicated via noticeboards and on all relevant Exercise Admin Instructions.									Ammunition store is secure, correct signs displayed. Immediate area kept unobstructed.
				Documented records of holdings maintained and regularly checked.									
				Authorised key holders published periodically on Part One Orders. Contraband box situated to prevent individuals from taking prohibited items into storage areas; (PEDs, lighters etc)									Checked & emptied regularly, documenting contents.
				Amnesty Box established with supporting orders for use.									
				Design and installation compliant with the requirements of Ref F. (Secured and tamper proof) Amnesty box use detailed in all range related training instructions. (Not to be used as the default disposal route)									
				Internal size and aperture do not permit large drops or large natures to be deposited or the unauthorised removal of contents.									
				Capacity for infantry common natures, pyrotechnics, and SAA only.									
				Class 1 SEAP approved padlock. Used to secure Amnesty box. Conspicuously marked and									

(a)	(b)	(c)	(d)	(e)	(f)	(g)	(h)	(i)	(j)	(k)	(I)	(m)	(n)
Ref	Activity / element (Step 1a)	Hazards identified (Step 1b)	Who or what might be harmed and how, e.g.	Existing control measures (Step 3a)		ssessmen		Is residual risk acceptable in the context of risk	Reasonable additional controls		ment with a		List required action(s) to instigate controls
			Military personnel - fatality Civ staff / contractors - injury General public - injury Environment - spill (Step 2)		L (1 to 5) (Step 3b)	I (1 to 5) (Step 3c)	Score (L x I) (Step 3d)	appetite for the activity? (Yes / No) – Refer to Risk Score Calculation above If Yes, move to column (n). If No, identify additional controls (Step 3e)	that can be implemented to reduce risk to ALARP (Step 3f)	L (1 to 5) (Step 3g)	I (1 to 5) (Step 3h)	Score (L x I) (Step 3i)	(Štep 3j)
				easily identifiable.									
				No smoking/Vaping signs with prohibited distances prominently displayed.									
5	Chemicals fuels/oils	Inadequate storage, Synergistic effects with other products Failure to storage vessels	Corrective house alsie issiteties	The COSHH inventory is maintained in a current state with minimal quantities being held. Only authorised personnel deemed competent use these types of product.	1	2	2	Yes					QM/ RQMS/SQMS Ensure COSHH register is maintained, all COSHH storage facilities are displaying the correct signage which is in a good state of repair.
			Pollution of local drains, the aquifer and other ground surface pollution resulting in environmental damage.	Substances also documented in the USRP maintained by the QM/MTSNCO.									DSEAR RA in place requires to be reviewed Aug 24
			1 '	DSEAR risk assessments in place to cover those areas and substances that fall outside of the accepted safe operating envelope. (Quantity and type)									
				POL Storage conatiner LPG Cage Reacting to an emergency: Gas leak/ release									
				Fuel spill Terrorist incident training undertaken periodically with documented records maintained.									
				Spillage equipment and absorbents positioned to support planned, authorised vehicle maintenance and major holdings.									
				Drainage plans maintained and kept with the USRP or within the site SHEF folder.									
6	Biological	Extended periods with no use.		Water holding and storage tank temperatures monitored	1	3	3	Yes					QM/RQMS
		Failure of hot water system to maintain water temperatures. Dog and Clinical Waste	Possible exposure to legionella	under contract. Legionella monthly testing and flushing regime carried out under contract.									Manage the legionella contractors in consultation with RFCA. (Access, egress temperature thresholds and flushing regime)

(a)	(b)	(c)	(d)	(e)	(f)	(g)	(h)	(i)	(j)	(k)	(I)	(m)	(n)
Ref	Activity / element (Step 1a)	Hazards identified (Step 1b)	Who or what might be harmed and how, e.g.	Existing control measures (Step 3a)		ssessmen xisting co		Is residual risk acceptable in the context of risk	Reasonable additional controls		ment with a trol measur		List required action(s) to instigate controls
			Military personnel - fatality Civ staff / contractors - injury General public - injury Environment - spill (Step 2)		L (1 to 5) (Step 3b)	I (1 to 5) (Step 3c)	Score (L x I) (Step 3d)	appetite for the activity? (Yes / No) – Refer to Risk Score Calculation above If Yes, move to column (n). If No, identify additional controls (Step 3e)	that can be implemented to reduce risk to ALARP (Step 3f)	L (1 to 5) (Step 3g)	(1 to 5) (Step 3h)	Score (L x I) (Step 3i)	(Štep 3j)
			health concerns. Exposure to low level.	Local flushing regime introduced and documented for extended periods of absence or non occupancy in liasion with the RQMS. Clinical Haz waste contract in place for disposal of clinical waste including sanitary waste. Dog Policy in place to ensure the control of dogs on site and disposal of dog waste. Update regarding dog in the WP on orders and during WIP induction.									Clinical Haz waste and sanitary waste disposal contract with Cathedral Hygiene. Dog register in place.
7	Asbestos	Disturbance of areas recognised as containing ACM	airborne asbestos fibres or dust resulting in the thickening of the	Site asbestos register maintained, information briefed to contractors & maintenance workers as part of the 4Cs brief. Management survey monitoring carried out under contract through RFCA, survey report produced and communicated during 4Cs. Areas containing or suspected of containing Asbestos or Asbestos Containing Materials (ACM) are documented and signs displayed. RFCA are aware of their responsibilties to employ competent contractors for maintenance tasks.	1	3	3	Yes					QM/RQMS Monitor & manage in line with survey report in consultation with RFCA
8	Radiation	Breakages of equipment exposing radioactive materials.	Site personnel (mil and civil servants), visitors or site contractors or tresspassers Cuts, lacerations, and possible exposure to minimal but low-level radioactive materials.	Inventory of holdings maintained by RQMS/SQMS on behalf of the Site Manager and Radiation Safety Officer. Areas containing radioactive equipment have appropriate signs displayed.	1	3	3	Yes					QM/WPS HoE appointed suitably trained persons Ensure handling procedures are understood & complied with.

(a)	(b)	(c)	(d)	(e)	(f)	(g)	(h)	(i)	(j)	(k)	(I)	(m)	(n)
Ref	Activity / element (Step 1a)	Hazards identified (Step 1b)	Who or what might be harmed and how, e.g.	Existing control measures (Step 3a)		ssessmen xisting co		Is residual risk acceptable in the context of risk	Reasonable additional controls		ment with a trol measur		List required action(s) to instigate controls
			Military personnel - fatality Civ staff / contractors - injury General public - injury Environment - spill (Step 2)		L (1 to 5) (Step 3b)	I (1 to 5) (Step 3c)	Score (L x I) (Step 3d)	appetite for the activity? (Yes / No) – Refer to Risk Score Calculation above If Yes, move to column (n). If No, identify additional controls (Step 3e)	that can be implemented to reduce risk to ALARP (Step 3f)	L (1 to 5) (Step 3g)	I (1 to 5) (Step 3h)	Score (L x I) (Step 3i)	(Step 3j)
9	Pathways and Roads	Poor state of repair. Inadequate lighting	Vehicle damage or pedestrian injuries arising from poorly maintained and deteriorating internal roads and pathways. Slips, trips and falls, sprains, strains, fractures or other muscular skeletal injuries.	Controlled access to places with radio active holdings. GTLS breakage kits located in areas where such equipment is held or stored. Annual return of holdings submitted to AWE through QM. Qualified personnel appointed in key radiation safety appointments. WPS Condition of roads, paths, gangways, stairs, etc monitored and maintained through the QM/RQMS in liaison with RFCA. Emergency access routes kept clear of obstructions at all times. Access to high places restricted/controlled through the QM. (Solar panels/ Phone/ comms masts) Site speed limited; controlled access, limited real estate, speed limits displayed. Separate pedestrian gates provided. Hedges and perimeter fence line maintained under contract or agreement with RFCA/ Highways agency.	1	3	3	Yes					Site Manager Routine checks and liaison with RFCA regarding infrastructure. QM to review Snow and Ice plan. Communication of Snow and Ice Plan.
10	Forklift Truck	Unauthorised or	Site personnel (mil and civil	Essential paths and roads included in Ice and Snow Clearance Plan. Access to vehicles, plant &	1	3	3	Yes					QM/MT SNCO/ Line
	Pressure Washer	incorrect use. Poorly maintained. Theft or tampering	servants), visitors or site contractors or tresspassers Impact, crush, or collision type	equipment restricted to authorised and appropriately licensed staff. Fork Lift Truck(FLT) is only operated by qualified (Licensed) and trained	•	J		163					Managers. Responsible for ensuring compliance with user, maintenance, and local security instructions.

(a)	(b)	(c)	(d)	(e)	(f)	(g)	(h)	(i)	(j)	(k)	(I)	(m)	(n)
Ref	Activity / element	Hazards identified	Who or what might be harmed	Existing control measures		ssessmen		Is residual risk acceptable	Reasonable		ment with a		List required action(s)
	(Step 1a)	(Step 1b)	and how, e.g. • Military personnel - fatality • Civ staff / contractors - injury • General public - injury • Environment - spill (Step 2)	(Step 3a)	L (1 to 5) (Step 3b)	I (1 to 5) (Step 3c)	Score (L x I) (Step 3d)	in the context of risk appetite for the activity? (Yes / No) – Refer to Risk Score Calculation above If Yes, move to column (n). If No, identify additional controls (Step 3e)	additional controls that can be implemented to reduce risk to ALARP (Step 3f)	L (1 to 5) (Step 3g)	I (1 to 5) (Step 3h)	Score (L x I) (Step 3i)	to instigate controls (Step 3j)
			Thermal burns, electrocution, muscular skeletal disorder from manoeuvring it into position.	operators/ drivers. Speed limits adhered to at all times, Safe Working Load (SWL) clearly displayed and adhered to. Driver always face the direction of travel, travelling with the forks down but off the ground. No sudden braking or high speed cornering, FLT is securely parked with keys									
				removed when not in use. All plant and equipment is in date for servicing, inspection, testing & maintenance in line with regulatory and manufacturuers requirements.									
				Pedestrian walkways are not impinged upon during lifting or manoevering. (where this is not possible alternative temporary pedestrian walk ways are put in place and cordoned off). Pressure washer only									
				operated by those deemed competent. Electrical tested before use results sent to (RFCA)									
				Personal Protective Equipment (Eye wear and gloves) issued with the pressure lance for washer use. (Eye protection mandatory)									
				Operator appropriately dressed, long sleeves, no shorts, suitable footwear. SSW & quick user guide									
				briefed, copy displayed at or inside the storage point. No detergents are used with the Pressure Washer.									

(a)	(b)	(c)	(d)	(e)	(f)	(g)	(h)	(i)	(j)	(k)	(1)	(m)	(n)
Ref	Activity / element (Step 1a)	Hazards identified (Step 1b)	Who or what might be harmed and how, e.g.	Existing control measures (Step 3a)		ssessmen		Is residual risk acceptable in the context of risk	Reasonable additional controls		ment with a		List required action(s) to instigate controls
			Military personnel - fatality Civ staff / contractors - injury General public - injury Environment - spill (Step 2)		L (1 to 5) (Step 3b)	I (1 to 5)	Score (L x I) (Step 3d)	appetite for the activity? (Yes / No) – Refer to Risk Score Calculation above If Yes, move to column (n). If No, identify additional controls (Step 3e)	that can be implemented to reduce risk to ALARP (Step 3f)	L (1 to 5) (Step 3g)	I (1 to 5) (Step 3h)	Score (L x I) (Step 3i)	(Štep 3j)
				Stock and trigger held during use; hands are not to be placed on the lance.									
11	Deteriorating condition of Building & Estate	Loss of services or building integrity.	Military Staff. Civil Servants Contractors and Visitors Ingress of water, loss of services resulting in reduced or loss of capability and Output.	Estate and building maintenance works monitored as part of periodic management checks by both the Regt and RFCA. Derelict or dangerous buildings or areas are secured to prevent unauthorised access or tresspass. Defence Fire & Rescue (DFR) consulted before any planned building works or signifiacnt changes of use. Dangerous or hazardous trees or shrubs (fire or falling) notified to RFCA for further investigation/ action. Signs & notices posted as and where required.	1	3	3	Yes					QM/RQMS Maintain regular checks of site infrastructure, keeping RFCA briefing on condition changes.
12	keeping	Poorly maintained infrastructure, accumulation of debris.	Military Staff. Civil Servants Contractors and Visitors Slips, trips, falls, fire loading, being hit by falling objects, harbourage of food pests from accumulated kitchen waste.	Waste managed in line with local authority waste contractor through RFCA. Hazardous waste appropriately stored with disposal through DESA. QM/ RQMS monitors waste procedures and evidence of fly tipping on site. Segregated waste areas Area inspections. Ground maintenance programme managed through RFCA. Site storage (Shelving or Racking) maintained with documented management checks of all significant configurations.	1	3	3	Yes					QM/RQMS Promote and maintain a sensible approach to general workspace safety and cleanliness.

(a)	(b)	(c)	(d)	(e)	(f)	(g)	(h)	(i)	(j)	(k)	(1)	(m)	(n)
Ref	Activity / element (Step 1a)	Hazards identified (Step 1b)	Who or what might be harmed and how, e.g. • Military personnel - fatality	Existing control measures (Step 3a)		ssessmen		Is residual risk acceptable in the context of risk appetite for the activity?	Reasonable additional controls that can be		ment with a trol measur		List required action(s) to instigate controls (Step 3j)
			Civ staff / contractors - injury General public - injury Environment - spill (Step 2)		L (1 to 5) (Step 3b)	I (1 to 5) (Step 3c)	Score (L x I) (Step 3d)	(Yes / No) – Refer to Risk Score Calculation above If Yes, move to column (n). If No, identify additional controls (Step 3e)	implemented to reduce risk to ALARP (Step 3f)	L (1 to 5) (Step 3g)	I (1 to 5) (Step 3h)	Score (L x I) (Step 3i)	(Step 3J)
13		Unauthorised access, low lying fumes or gases.	Military Staff. Civil Servants Contractors and Visitors Being overcome by fumes, becoming unconscious, fire or explosion. VSI or Fatality	Location of the sites recognised Confined Spaces (if any) are identified and managed under strict control by QM. When authorised works are being carried out, they are supported by a Permit to Work (PTW) issued by RFCA to cover the specific tasks. 4Cs delivered to all contractors. Safe Systems of Work Only those providing the correct authoritative paperwork through RFCA will be permitted access to work in the recognised Confined Spaces.	1	4	4	Yes					RFCA responsible for issuing PTW to all contractors across the site.
14	Electrical Installation & Supply	Faulty electrics Overloading Overriding safety devices	Site personnel (mil and civil servants), visitors or site contractors or tresspassers. VSI or fatality Electric shock, electrical burns, accumulation of hydrogen gas, electrical shorting, propagation of fire or explosion or complete loss of power.	Underground servcies are known and mapped by RFCA. Inspection, testing and maintenance programme in place for electrical installations, static equipment and portable appliances. Lightning conductors installed and maintained. RFCA issue a statement of known hazards to all contractors carrying out excavation/ ground breaking maintenance on site. (Site Manager informed) Signs & notices posted where applicable. Portable appliances are managed through a testing programme under contract. Electrical Equipment Inspection & Testing (EEIT) Isolating/ shut off switches identified and communicated	1	4	4	Yes					QM/ RFCA Ensure EEIT register remains in date through consultation with RFCA. Control for those bringing in Portable Electrical Appliances.

(a)	(b)	(c)	(d)	(e)	(f)	(g)	(h)	(i)	(j)	(k)	(I)	(m)	(n)
Ref	Activity / element (Step 1a)	Hazards identified (Step 1b)	Who or what might be harmed and how, e.g.	Existing control measures (Step 3a)		ssessmen		Is residual risk acceptable in the context of risk	Reasonable additional controls		ment with a		List required action(s) to instigate controls
			Military personnel - fatality Civ staff / contractors - injury General public - injury Environment - spill (Step 2)		L (1 to 5) (Step 3b)	I (1 to 5) (Step 3c)	Score (L x I) (Step 3d)	appetite for the activity? (Yes / No) – Refer to Risk Score Calculation above If Yes, move to column (n). If No, identify additional controls (Step 3e)	that can be implemented to reduce risk to ALARP (Step 3f)	L (1 to 5) (Step 3g)	I (1 to 5) (Step 3h)	Score (L x I) (Step 3i)	(Step 3j)
				via the SHEF noticeboard as part of the Emergency Procedures.									
				Battery charging is carried out in a suitably constructed building away from combustible materials.									
15	Mains Gas Supply	Loss of supply	Site personnel (mil and civil servants), visitors or site	Gas Underground pipe runs mapped and held by RFCA.	1	2	2	Yes					QM/RQMS
		Gas leak from damaged mains	contractors or tresspassers Potential for the creation of an	Plant room secured with controlled access for maintenance and servicing activity.									Monitor and manage access and servicing through RFCA.
			area or space. Propagation of fire from ignition from leaking or damaged gas main or pipework.	Signs and barriers erected and displayed as and where required. (No Smoking/Vaping, naked flames, Asbestos etc)									
16	Pressurised Gas (LPG)	Incorrect storage procedures	Site personnel (mil and civil servants), visitors or site	LPG quantities kept to a working minimum.	1	4	4	Yes					QM/RQMS
		Excessive quantities being stored	contractors or tresspassers	LPG stored outside in a secure gas storage cage,									Gas ordered and used when needed.
		Fire and Explosion	VSI or fatality	displaying the appropriate safety and warning signage.									F&L manager to ensure strict control
			Propagation of fire or creation of an explosive atmosphere.	Signs and notices posted. Inspection process in place.									
			Synergy with other products in storage.	mopositori processe in place.									
			Muscular skeletal injury.										
17	Storage Tanks	Environmental surface and ground contamination	Site personnel (mil and civil servants), visitors or site contractors or tresspassers	Oil Water Interceptors maintained under contract.	1	3	3	Yes					Engage with RFCA to maintain Interceptor/
			Diesel vehicle fleet, no significant risk from accumulation of low-lying fumes	Vehicle washdown point drains within the vicinty of Interceptors.									separator servicing.
			to create an explosive atmosphere.	(Residues and particulates from vehicle run off, no detergents used).									
18	Falls and Falling Objects	Unsafe or unauthorised working practices.	Site personnel (mil and civil servants), visitors or site contractors or tresspassers	Access to high levels and roof areas strictly controlled by the QM.	1	5	5	Yes					QM/RQMS Ensure access equipment remains in

(a)	(b)	(c)	(d)	(e)	(f)	(g)	(h)	(i)	(j)	(k)	(1)	(m)	(n)
Ref	Activity / element (Step 1a)	Hazards identified (Step 1b)	Who or what might be harmed and how, e.g.	Existing control measures (Step 3a)	es Assessment with existing controls			Is residual risk acceptable in the context of risk	additional controls	Reassessment with additional control measures			to instigate controls
			Military personnel - fatality Civ staff / contractors - injury General public - injury Environment - spill (Step 2)		L (1 to 5) (Step 3b)	I (1 to 5) (Step 3c)	Score (L x I) (Step 3d)	appetite for the activity? (Yes / No) – Refer to Risk Score Calculation above If Yes, move to column (n). If No, identify additional controls (Step 3e)	that can be implemented to reduce risk to ALARP (Step 3f)	L (1 to 5) (Step 3g)	I (1 to 5) (Step 3h)	Score (L x I) (Step 3i)	(Step 3j)
		Use of defective equipment Adverse environmental conditions	Falling from height, impact type injuries from being struck by falling objects. VSI or Fatality	RFCA authorise all engineering contractors employed to carry out work at height. (Competence) Only authorised working at height takes place. All height access equipment (ladders, mobile steps with fall or guard rails or other platforms) is maintained (Inspected and checked) in line with service/manufacturers instructions. Warning and restriction signs & notices posted as and where required. Shelving stacked sensibly heavy low, lighter higher within SWL thresholds. Management checks in place to monitor serviceability of significant shelving configurations. (Register)									good working order.
19	Contractors and Visitors	Unauthorised works Wilful or reckless damage Theft	Site personnel (mil and civil servants), visitors or site contractors or tresspassers Personal Injury, or injury of a third party whilst carrying out their work, or through their presence, authorised or otherwise. VSI or Fatality	Access controlled at point of entry. 4Cs procedures used for booking in. Site safety and emergeny procedures briefed. Specific hazards and supporting information briefed; supported by this document. RFCA authorise all PTW activities that contractors are employed to carry out. Signs & notices displayed as and where required. Alternative Venue (AV) users are familiarised with site procedures by the Site Manager. AV use is agreed by the QM, but formally contracted directly through RFCA.		5	5	Yes					QM as the 4Cs appointed Person is to ensure these procedures remain current. Strict access at main gate. RFCA are to ensure regular contractors are inducted accordingly

(a)	(b)	(c)	(d)	(e)	(f)	(g)	(h)	(i)	(j)	(k)	(1)	(m)	(n)
Ref	Activity / element (Step 1a)		and how, e.g.		Assessment with existing controls			Is residual risk acceptable in the context of risk	Reasonable additional controls that can be implemented to reduce risk to ALARP (Step 3f)	Reassessment with addit control measures			List required action(s) to instigate controls
				L (1 to 5) (Step 3b)	I (1 to 5) (Step 3c)	Score (L x I) (Step 3d)	appetite for the activity? (Yes / No) – Refer to Risk Score Calculation above If Yes, move to column (n). If No, identify additional controls (Step 3e)	L (1 to 5) (Step 3g)		I (1 to 5) (Step 3h)	Score (L x I) (Step 3i)	(Štep 3j)	
				Access for out of hours AV use requires a repsonsible Point of Contact, unless otherwise agreed locally with the caretaker or other military site personnel.									
20	Emissions & Processes	Extended running times for idling vehicles. Spills or leakages of POL from containers of vehicles.	Site personnel (mil and civi servants), visitors or site contractors or tresspassers Air, surface, ground and ac pollution, potential loss of wildlife and contamination water supplies. Possible enforcement action the EA, reputational loss ar financial costs for cleaning decontamination.	recognised and controlled in line with the CO commitment to Sustainable Development communicated through their SHEF statement. Process waste identified and controlled through the QM/RQMS(Storage and Disposal) using the DESA process.		3	3	Yes					Site Manager To ensure that records of hazardous waste transactions are kept.
21	Provision of First Aid	Cardiac Arrest, Serious, and minor injuries VSI or Fatality	Site personnel (mil and civi servants), visitors or site contractors or tresspassers Cardiac Arrest possible	Mil Persons do Battlefield	1	5	5						QM/LM are to identify when staff require refresh training, or a new First Aider nominated when one leaves.
Authori	Authorising Officer / Warrant Officer / NCO (at unit level) No, Rank, Name						Post		Date		Signatur	e ¹	
Existing and additional controls agreed Maj Johnson						2IC		21 Aug 24		A Johnson			
Where	risk is elevated up the Co	oC, CO to confirm addition	al controls implemented										

¹ Can be electronic signature.

NOTES

Risk = Likelihood x Impact

Likelihood		Definition				
5 Highly Probable (Almost Certain) Is expected to occur in most circumstances		Is expected to occur in most circumstances				
4 Probable		Will probably occur at some time, or in most circumstances				
3 Possible		Fairly likely to occur at some time, or some circumstances				
2 Unlikely		Is unlikely to occur, but could occur at sometime				
1 Remote / Rare May only occur in exceptional circumstant		May only occur in exceptional circumstances				

Impact		Definition (Health Safety and Environment)						
5	Critical	 Multiple fatalities or permanent, life changing injuries. Permanent loss or damage beyond remediation of an important and publicly high-profile natural resource, area or species. Multiple incidents causing a major environmental impact. 						
4	Severe	 A single death or multiple life-threatening injuries. Severe damage over a wide area and/or on a prolonged basis to a natural resource, including controlled waters, or geography requiring multi-year remediation. Single incident causing a major environmental effect or multiple incidents causing significant effect. 						
3	Major	 Single life changing injury or multiple injuries which have a short-term impact on normal way of or quality of life. Moderate damage to an extended area and/or area with moderate environmental sensitivity (scarce/ valuable) requiring months of remediation. Single incident causing significant environmental impact. 						
2	Moderate	 Multiple injuries requiring first aid. Moderate damage to an area, and that can be remedied internally. Multiple incidents causing minor environmental effect. 						
1	Minor	 An Injury requiring first aid Limited short-term damage to an area of low environmental significance/ sensitivity Incidents causing minor environmental impacts 						

Step 5 - Review the generic risk assessment and update if necessary - All generic risk assessments should be regularly reviewed at a frequency proportional to the risk prior to any controls being proposed. In practice generic risk assessments should be reviewed at least annually, or more frequently:

- where required by local instructions/procedures.
- if the safe execution of the activity relies on stringent supervision and/or adherence to a safe system of work.
- if there is reason to doubt the effectiveness of the assessment.
- following an accident or near miss.
- following significant changes to the task, process, procedure, equipment, personnel, or management.
 following the introduction of more vulnerable personnel (e.g., persons under 18 or pregnant persons).

Risk Management							
Risk Rating	Authorisation	How Risk should be managed					
1 – 3 (Very Low)	LCpl - Capt						
4 – 6 (Low)	OF3 Sub-Unit Comd, Unit 2IC and XO	Review periodically to ensure conditions have not changed and working within ALARP and risk appetite.					
7 – 9 (Low - Medium)	OF4 CO and Sub-Unit Comds with delegated powers						
10 – 14 (Medium)	OF5 / 1* Commander	<u>Good risk mitigations</u> to ensure that the impact remains ALARP and tolerable. Reassess frequently to ensure conditions remain the same.					
15 – 19 (Medium to High)	2* Div HQ	Requires active management – review of desired outcome with additional resources or change to output requirements.					
20 (High)	3*/2* Commanders HC, Fd Army & JHC	<u>Contingency plans</u> may suffice together with limited risk mitigations to achieve risk ALARP and tolerable.					
25 (Very High)	4* CGS	Operational capability where the required outcome impacts on defined military capability.					